

Politecnico di Bari

Repository Istituzionale dei Prodotti della Ricerca del Politecnico di Bari

Hydraulic Characterization of a Pervious Concrete for Deep Draining Trenches

This is a post print of the following article

Original Citation:
Hydraulic Characterization of a Pervious Concrete for Deep Draining Trenches / Marzulli, V., Cafaro, F., Ziccarelli, M.. - In: JOURNAL OF MATERIALS IN CIVIL ENGINEERING. - ISSN 0899-1561. - STAMPA. - 30:6(2018). [10.1061/(ASCE)MT.1943-5533.0002274]

Availability:
This version is available at http://hdl.handle.net/11589/118254 since: 2021-03-11

Published version
DOI:10.1061/(ASCE)MT.1943-5533.0002274

Publisher:

Terms of use:

(Article begins on next page)

17 November 2026

Journal of Materials in Civil Engineering

Hydraulic Characterization of a Pervious Concrete for Deep Draining Trenches

--Manuscript Draft--

Manuscript Number:	MTENG-6264R2
Full Title:	Hydraulic Characterization of a Pervious Concrete for Deep Draining Trenches
Manuscript Region of Origin:	ITALY
Article Type:	Technical Paper
Section/Category:	Section A: Cementitious/Brittle matrix (includes all forms of concrete)
Funding Information:	MIUR (Italy) ((PRIN 2010-2011: prot. 2010SWTCKC_010)) — Not applicable
Abstract:	Reduction of pore water pressures is a useful strategy to improve the stability of slopes. Deep draining trenches can be used for this scope. For the realisation of deep trenches, the usual conventional construction techniques are not adequate and the use of adjacent vertical panels, built by means of the methods well established for diaphragm walls, is necessary. However, unbonded materials (i.e. gravels) cannot be used, since the excavation of a panel adjacent to already built ones will cause instability. For this scope a bonded material such as the pervious concrete can be used. It must have high permeability, filtering capacity in order to prevent the internal erosion of the soil in which the trench drain is installed, sufficient shear strength after a short curing time avoiding the instability of adjacent previously built panels. This paper reports the hydraulic characterization of two mixtures of pervious concrete carried out in the laboratory. The hydraulic conductivity has been measured in saturated conditions. Then, the water retention functions of the mixtures have been experimentally deduced, by investigating different calculation options, and their impact on the simulation of seepage processes through an unsaturated soil mass, in which an ideal trench is located, has been studied.
Corresponding Author:	Francesco Cafaro Politecnico di Bari Bari, ITALY
Corresponding Author E-Mail:	francesco.cafaro@poliba.it
Order of Authors:	Valentina Marzulli Francesco Cafaro Maurizio Ziccarelli
Suggested Reviewers:	
Opposed Reviewers:	
Additional Information:	
Question	**Response**
Authors are required to attain permission to re-use content, figures, tables, charts, maps, and photographs for which the authors do not hold copyright. Figures created by the authors but previously published under copyright elsewhere may require permission. For more information see http://ascelibrary.org/doi/abs/10.1061/9780784479018.ch03. All permissions must be uploaded as a permission file in PDF format. Are there any required permissions that have not yet been secured? If yes, please explain in the	No

Powered by Editorial Manager® and ProduXion Manager® from Aries Systems Corporation

comment box.	
ASCE does not review manuscripts that are being considered elsewhere to include other ASCE Journals and all conference proceedings. Is the article or parts of it being considered for any other publication? If your answer is yes, please explain in the comments box below.	No
Is this article or parts of it already published in print or online in any language? ASCE does not review content already published (see next questions for conference papers and posted theses/dissertations). If your answer is yes, please explain in the comments box below.	No
Has this paper or parts of it been published as a conference proceeding? A conference proceeding may be reviewed for publication only if it has been significantly revised and contains 50% new content. Any content overlap should be reworded and/or properly referenced. If your answer is yes, please explain in the comments box below and be prepared to provide the conference paper.	No
ASCE allows submissions of papers that are based on theses and dissertations so long as the paper has been modified to fit the journal page limits, format, and tailored for the audience. ASCE will consider such papers even if the thesis or dissertation has been posted online provided that the degree-granting institution requires that the thesis or dissertation be posted. Is this paper a derivative of a thesis or dissertation posted or about to be posted on the Internet? If yes, please provide the URL or DOI permalink in the comment box below.	No
Each submission to ASCE must stand on its own and represent significant new information, which may include disproving the work of others. While it is acceptable to build upon one's own work or replicate other's work, it is not appropriate to fragment the research to maximize the number of manuscripts or to submit papers that represent very small incremental changes. ASCE may use tools such as CrossCheck, Duplicate Submission Checks, and Google Scholar to verify that submissions are novel. Does the manuscript constitute incremental	No

work (i.e. restating raw data, models, or conclusions from a previously published study)?	
Authors are expected to present their papers within the page limitations described in <u>Publishing in ASCE Journals: A Guide for Authors</u>. Technical papers and Case Studies must not exceed 30 double-spaced manuscript pages, including all figures and tables. Technical notes must not exceed 7 double-spaced manuscript pages. Papers that exceed the limits must be justified. Grossly over-length papers may be returned without review. Does this paper exceed the ASCE length limitations? If yes, please provide justification in the comments box below.	No
All authors listed on the manuscript must have contributed to the study and must approve the current version of the manuscript. Are there any authors on the paper that do not meet these criteria? If the answer is yes, please explain in the comments.	No
Was this paper previously declined or withdrawn from this or another ASCE journal? If so, please provide the previous manuscript number and explain what you have changed in this current version in the comments box below. You may upload a separate response to reviewers if your comments are extensive.	Yes
Please provide the previous manuscript number and explain what you have changed in this current version in the comments box below. You may upload a separate response to reviewers if your comments are extensive. as follow-up to "Was this paper previously declined or withdrawn from this or another ASCE journal? If so, please provide the previous manuscript number and explain what you have changed in this current version in the comments box below. You may upload a separate response to reviewers if your comments are extensive. "	Previous manuscript: MTENG-6014. The authors have provided more technical details and interpretations, as requested by the reviewers. Moreover, improvement of some figures and integration of references have been carried out. The list of symbols has been removed and the symbols have been defined in the text.
Companion manuscripts are discouraged as all papers published must be able to stand on their own. Justification must be provided to the editor if an author feels as though the work must be presented in two parts and published simultaneously.	

There is no guarantee that companions will be reviewed by the same reviewers, which complicates the review process, increases the risk for rejection and potentially lengthens the review time. If this is a companion paper, please indicate the part number and provide the title, authors and manuscript number (if available) for the companion papers along with your detailed justification for the editor in the comments box below. If there is no justification provided, or if there is insufficient justification, the papers will be returned without review.	
If this manuscript is intended as part of a Special Issue or Collection, please provide the Special Collection title and name of the guest editor in the comments box below.	
Recognizing that science and engineering are best served when data aremade available during the review and discussion of manuscripts andjournal articles, and to allow others to replicate and build on workpublished in ASCE journals, all reasonable requests by reviewers formaterials, data, and associated protocols must be fulfilled. If you are restricted from sharing your data and materials, please explain below.	
Papers published in ASCE Journals must make a contribution to the core body of knowledge and to the advancement of the field. Authors must consider how their new knowledge and/or innovations add value to the state of the art and/or state of the practice. Please outline the specific contributions of this research in the comments box.	The work should give a contribution in the field of the slope stabilization by deep draining trenches made of pervious concrete. The simulation of seepage through the unsaturated soil portion could be improved by the results of this research.
The flat fee for including color figures in print is $800, regardless of the number of color figures. There is no fee for online only color figures. If you decide to not print figures in color, please ensure that the color figures will also make sense when printed in black-and-white, and remove any reference to color in the text. Only one file is accepted for each figure. Do you intend to pay to include color figures in print? If yes, please indicate which figures in the comments box.	No
If there is anything else you wish to communicate to the editor of the journal, please do so in this box.	

Manuscript
Click here to download Manuscript MTENG-6264-NOVEMBER6 Revised Manuscript.docx

Hydraulic Characterization of a Pervious Concrete for Deep Draining Trenches

V. Marzulli (*), F. Cafaro (**), M. Ziccarelli (***)

(*) Valentina Marzulli, PhD student
Friedrich-Alexander Universität Erlangen-Nürnberg, Institute for Multiscale Simulation, Erlangen (Germany), formerly at Technical University of Bari, Italy

e-mail: valentina.marzulli@fau.de

(**) Francesco Cafaro, Assistant Professor
DICATECh – Technical University of Bari, Bari, Italy e-mail: francesco.cafaro@poliba.it

(***) Maurizio Ziccarelli, Assistant Professor
DICAM – University of Palermo, Palermo, Italy e-mail: maurizio.ziccarelli@unipa.it

Contact address:

Dr. Francesco Cafaro – DICATECh – POLITECNICO DI BARI

Via Orabona 4, 70125 Bari (Italy)

Phone (0039)0805963300 E-mail: francesco.cafaro@poliba.it

ABSTRACT

Reduction of pore water pressures is a useful strategy to improve the stability of slopes. Deep draining trenches can be used for this scope. For the realisation of deep trenches, the usual conventional construction techniques are not adequate and the use of adjacent vertical panels, built by means of the methods well established for diaphragm walls, is necessary. However, unbonded materials (i.e. gravels) cannot be used, since the excavation of a panel adjacent to already built ones will cause instability. For this scope a bonded material such as the pervious concrete can be used. It must have high permeability, filtering capacity in order to prevent the internal erosion of the soil in which the trench drain is installed, sufficient shear strength after a short curing time avoiding the instability of adjacent previously built panels. This paper reports the hydraulic characterization of two mixtures of pervious concrete carried out in the laboratory. The hydraulic conductivity has been measured in saturated conditions. Then, the water retention functions of the mixtures have been experimentally deduced, by investigating different calculation options, and their impact on the simulation of seepage processes through an unsaturated soil mass, in which an ideal trench is located, has been studied.

KEYWORDS

Pervious concrete; deep trenches; drainage; porosity; hydraulic conductivity; suction.

INTRODUCTION

The stability of soil slopes can be effectively enhanced by reducing the pore water pressures within the soil mass, since its shear strength depends on the effective stresses (Terzaghi, 1950). For this purpose, different solutions can be adopted, such as draining galleries, sub-horizontal drainholes and draining trenches (Kenney et al., 1977; Nonveiller, 1981; Lau and Kenney, 1984; Burghignoli and Desideri, 1987; Di Maio et al., 1988; Nakamura, 1988; Rahardjo et al., 2003; González de Vallejo et al., 2005; Tsao et al., 2005; D'Acunto and Urciuoli, 2006; Valore and Ziccarelli, 2015; Cotecchia et al., 2016). Draining trenches, also called trench drains (Hutchinson, 1977), essentially working based on gravity seepage, are often the most convenient solution when the slope is not steep or very steep. For excavations deeper than 5-6 m, draining trenches are usually built by means of the same equipment available for the realisation of secant piles and diaphragm walls.

As it is well known, the construction phases of a deep drain trench (consisting of contiguous vertical panels) are the following:

a) the odd panels (panels 1 and 3, Fig. 1) are first constructed;

b) afterwards the even panels are realised (panel 2 between the two already realised panels 1 and 3 in Fig. 1).

In the case of Fig. 1a, even if the excavation is performed in presence of temporary support, for example by using polymeric slurry, instability of the filling of panels 1 and 3 may occur when it is made of cohesionless material (Valore et al., 2017b). If the filling material has sufficient shear strength and stiffness, the excavation of the intermediate panel (panel 2 in Fig. 1b) can be carried out without instabilising the already built panels 1 and 3. Partially bonded granular particles (involving true cohesion), interconnected pores and good permeability characteristics are the other requirements of a good filling material. For these purposes the pervious concrete can be effectively employed. Pervious concrete has long been used in other fields of civil engineering, such as draining road pavements, residential roads, driveways, sidewalks, tennis courts, sustainable constructions, etc.. Research has been extensively performed in those fields, essentially focusing on no-fines concrete (containing no or small amounts of sand) which has high permeability (Tennis et al., 2004; Haselbach et al., 2006; Kevern, 2006; Schaefer et al., 2006; Chen et al., 2008; Collins et al., 2008; Haselbach, 2010; Martin III et al., 2014; Mrakovcic et al., 2014; Chandrappa and Biligiri, 2016).

Pervious concrete differs from the conventional concrete in some properties such as lower density (1400-2000 kg/m^3), higher porosity and (normally) lower compressive strength (Ghafoori and Dutta, 1995; Abadjieva and Sephiri, 2000; Mageswari et al., 2016). The porosity of pervious concrete ranges from 15 to 30% (Haselbach and Freeman, 2006; Neithalath et al. 2010); the diameter of pores ranges from 1.5 to 8 mm (Sommerville et al., 2011; Martin III et al., 2013; Torres et al., 2015). Moreover, it is a good environmental and sustainable material (Neithalath, 2004; Goel, 2006; Neithalath et al., 2010; Haselbach et al., 2011; Shu et al., 2011; ACPT, 2012; Nemirovsky et al., 2013; Barnhouse and Srubar, 2016). However, when employed as filling material for draining trenches, it must protect the soil surrounding the trench (i.e. the soil in which the trenches are installed) and hence it must also have good filter properties.

Valore et al. (2017b) reported an extensive laboratory investigation on the mix-design of pervious (or permeable) concrete that is able to meet both drainage and filter requirements which are well known in the field of earth dams (Fell et al., 2014), with reference to the saturated material. The results reported by Valore et al. (2017b) suggest that a pervious concrete, in order to satisfy the above-

mentioned requirements, must be realised with coarse aggregates (particle size typically from 2 to 60mm), sand ($0.06 < d < 2$ mm), cement and water. The addition of sand, or fine gravel (particle size from 2.5-5mm), is necessary when the pervious concrete has to work both as draining material and as protective filter. Results of this study also confirm the high variability of the hydraulic and mechanical properties with respect to conventional concrete. Some aspects, however, need to be thoroughly investigated, especially with regard to the partial saturation, which represents a condition that may occur in situ, at least temporarily and in some portions of the trenches. Besides, experimental research is needed to deepen the knowledge on the clogging resistance of the pervious concrete, especially for applications of draining trenches for clayey soils, and therefore on durability and environmental sustainability of this type of remedial works. Moreover, further research is necessary for a deeper study of the three dimensional variability of the hydraulic and mechanical characteristics when the concrete is cast in place and involves volumes much greater than those of laboratory specimens. This last point, along with the in situ installation technologies, will not be discussed here since they are out of the scope of this research. In this paper, results of an experimental study on the hydraulic (in both saturated and unsaturated conditions) properties of the pervious concrete and of a numerical study on the influence of these properties on the seepage regime within unsaturated soil mass, in which a trench drain is installed, are shown and discussed.

The hydraulic characterization for unsaturated conditions has been carried out on specimens of two different mixtures (two specimens for each mixture), while, for the determination of the saturated hydraulic conductivity and the mechanical properties of the mixtures, thirteen and sixteen specimens have been used, respectively. With respect to the unsaturated hydraulic characterization, although the number of the tested specimens is not high, also due to the time-consuming procedure, the authors consider the adopted methodology useful, particularly when stating the van Genuchten fitting parameters which are more affected by different options of interpolation. Indeed, the results should inform further and more extensive investigations.

MATERIALS

The studied pervious concrete is quite different from the common no-fines concretes, since the percentage of sand is predominant or very significant among the aggregates (Fig.2).

It has been made by using high early strength Portland cement Tecnocem II B-LL 32,5 R, (EN 197-1 – Cem II / B-LL 32,5). The cement composition, in terms of mass, is characterized by clinker (65% - 79%), limestone (21% - 35%), TOC (total organic carbon, $\leq 0.20\%$), minor constituents (including sulphates such as SO3, chlorides $\leq 0.10\%$). The aggregates are calcareous gravel and silica sand.

The grain size distribution of each aggregate and the resulting grading of the mixtures M1 and M2 are shown in Fig. 2. The composition of mixture M1 is the following: gravel 1 (d_{50}=7.7mm) 30% in weight, sand 1 (d_{50}=0.95mm) 70% in weight; that of mixture M2 is the following: gravel 2 (d_{50}=2.5mm) 50% in weight, sand 2 (d_{50}=0.45mm) 50% in weight. Further physical characteristics of the mixtures are summarized in Table 1.

As can be observed from Fig. 2, the grain size distribution of both mixtures M1 and M2 is gap graded. These particular granulometric distributions of the aggregates give rise to size and distribution of interconnected pores of the pervious concrete providing excellent permeability and resistance to clogging (Valore et al., 2017b).

All the specimens have been cast into testing cylindres (cylindrical PVC tubes) and gently compacted with three hammer hits. The specimens of mix M1 and M2 have been cured in air in the laboratory at a temperature of 20±1 °C and relative humidity of 45-50%. Other specimens, of the same mixture, have been put into pure water after 1 day since their preparation and left to cure completely submerged in the same water. The last represents a very extreme condition for the concrete of the trench, but allows to determine the minimum values of its mechanical properties. In fact, it is well known that the mechanical properties of the concrete (i.e. compressive strength and stiffness) are influenced by the water in which the curing takes place. In case of curing in pure water, the leaching of the free calcium hydroxide causes a reduction of strength.

The physical characteristics of the investigated specimens (Fig. 3) used for the unsaturated hydraulic characterisation are summarised in Table 1. The total porosity *n* was determined following the water displacements methodology suggested by Montes et al. (2005). These values of *n* are quite higher than the previously mentioned porosity range observed for pervious concretes used in other fields of civil engineering.

The most important characteristics governing both compressive strength and hydraulic conductivity of this kind of material are the overall porosity and the size and distribution of voids and interconnected voids (Ghafoori and Dutta, 1996; Abadjieva and Sephiri, 2000; Sommerville et al., 2011; Alam et al., 2012; Thakre et al., 2014; Ushane et al., 2014).

As can be observed in Fig. 4, the two mixtures show relatively different stress-strain curves, though many initial features are quite similar. The compressive strength σ_f of the M1 mixture is 1.16 MPa, while that of the M2 mixture is 1.92 MPa, measured at values of the axial strain of 0.7% and 0.4%, respectively. The secant stiffness *E* of M1 is 166 MPa while that of M2 is 480 MPa. Both compressive strength and stiffness of the two mixtures depend on size and distribution of pores that are relatively different, although their total porosities are similar. The maximum increase of both strength and

stiffness occurs in the early days of curing time. Considering all the results obtained in the tests, the uniaxial compressive strength is ranging from 0.5 to 3 MPa; the minimum values were recorded for specimens after two days of curing time. For the same mixtures and for the same curing time, differences even higher than 50% are recorded, depending on the overall porosity and size of voids. The compressive strength and stiffness of the mixtures ensure that the geotechnical system made by the panels (filled of pervious concrete) and by the surrounding soils will have adequate safety factors. The uniaxial compressive strength values fall in the typical ranges of σ_f of no-fines concretes with similar void ratio (Ghafoori and Dutta, 1996; Abadjieva and Sephiri, 2000; Kevern et al., 2008; Sommerville et al., 2011; Alam et al., 2012; Kevern and Farney, 2012; Singh and Scanlon, 2013; Thakre et al., 2014; Ushane et al., 2014; Zhong and Wille, 2016). Poisson's ratio ν can be assumed equal to that of the normal concrete (Mahesh and Lavanya, 2016) and equal to 0.2.

Considerations on the depth of the panels of the draining trenches that can be reached by using the pervious concrete as filling material can be done. It is well known that the height of a slope depends on the geometry of the problem, the mechanical properties of soils or rocks forming the slope, the presence of layering and discontinuity and, eventually, constitutive minor geological and geotechnical details (Terzaghi, 1929; Rowe, 1972; Leonards, 1982), the influence of the latter being sometimes very significant (Valore et al., 2017a; Ziccarelli et al., 2017). For homogeneous vertical slopes, such as the sides of panels 1 and 3, when the excavation of panel 2 is realized between them (see Figure 1b), and assuming a purely cohesive behaviour for the concrete, a partial factor of safety equal to one and neglecting positive 3D effects, the limit height, h_{lim}, is (Pastor et al., 2000):

$$h_{lim} = \frac{3.8\ c}{\gamma_c} \qquad \text{(Eq.1)}$$

in which c ($c=\sigma_f/2$) is the true cohesion of the concrete and γ_c is its unit weight.

Assuming a conservative value of the uniaxial compressive strength σ_f of 0.3 MPa (lower than the minimum value obtained after a curing time of 2 days in pure water), a critical value h_{lim} of 30m results for γ_c=19 kN/m^3. This calculation demonstrates that very deep trenches can be built safely and without long delays in the excavation of the even (or intermediate) panels as defined in Fig. 1. This allows an efficient and relatively inexpensive site planning.

METHODOLOGY

The hydraulic conductivity of pervious (no-fines) concrete has been studied by several authors with both the falling head permeameter and the constant head permeameter (Neithalath, 2004; Kevern,

2006; Haselbach, 2010; Deo et al., 2010; Coughlin et al., 2012; Martin III et al., 2014; Kevern, 2015; Chandrappa and Biligiri, 2016; West et al., 2016). In the present work, the hydraulic conductivity k_s of saturated specimens has been determined by means of the falling head permeameter, using the relative well known relationship. This relationship is valid under the assumption of laminar flow and the validity of Darcy's law. Montes and Haselbach (2006) demonstrated that the flow in pervious (no-fines) concrete normally falls within the laminar or at most in the transitory domain. Hence, it is applicable for the pervious concrete used in the experiments being the mean particles (and consequently the size of pores) smaller than the ones by which the no-fines concrete is made.

The analysis of the pervious concrete retention properties has been carried out, for specimens of mixture M1 (labelled as MP53 and MP5, Fig. 3) and M2 (labelled as MP54 and MP56, Fig. 3), by using the filter paper method (Chandler and Gutierrez, 1986). All the specimens have been initially subjected to the monitoring of the weight in order to obtain a reliable evaluation of the hygroscopic weight. This operation has been necessary because it was not possible to put the specimens in the oven to determine the dry weight since this could have led to the deterioration of the physical and chemical properties of the concrete.

The volumetric water content θ (equal to nS_r, where n is the porosity and S_r is the saturation degree) has been determined under the hypothesis that the void ratio remains constant during wetting due to the stiffness of the material. This hypothesis has been experimentally checked after the tests and it will be discussed later. Consistently, it has been possible to determine the volume of water to be dispensed to each specimen during the application of the filter paper method to induce a progressive wetting.

The suction ($s=u_a-u_w$,where u_a is the air pressure and u_w is the water pressure) measurements have been performed by means of the in-contact filter paper method (Chandler and Gutierrez, 1986) and they are representative of the matrix suction. The filter paper calibration employed to deduce the suction values is the one reported by Chandler et al. (1992) for filter paper Whatman n.42.

These tests have been carried out following the procedure suggested by Ridley (1993), which makes use of appropriately sealed perspex devices to place filter paper disks in contact with both the top and bottom of the specimen. A cling film has been used to isolate the specimens from the external environment, for a period of time greater than or equal to eight days.

During the tests, the estimated volume of water has been dispensed to the specimen via a syringe and the filter moisture, after equalization, has been measured at both top and bottom of the specimen and the corresponding suction has been determined as the average of the two values.

When the suction became negligible, it was possible to start the drying. The specimens have been left to dry for a period of time greater than or equal to two weeks. In this case, it was possible to calculate the average value of suction for each step of drying. The specimen MP54 has been subjected to a "3rd wetting" after previous cycles.

At the end of the tests, the specimens have been disgregated and measurements of their weight after drying in the oven at the temperature of 105°C have been carried out to allow the determination of the real dry weight. Moreover, a free swelling test carried out on a disgregated specimen, after removing the coarser fraction, has corroborated the hypothesis that the material has low swelling ability: a material column of about 30 mm diameter and 70 mm height has been put into a graduated cylinder and soaked with water and no swelling has been observed. This fact, along with the condition of partially bonded material for the pervious concrete, justifies the rigid skeleton assumption.

In the following, the pervious concrete hydraulic behaviour will be shown and discussed in terms of both saturated permeability and *volumetric water content* (θ) versus *suction* (s) relationship (i.e. water retention curve,WRC). Thereafter, the results of 2D finite element (FE) analyses of the transient seepage, carried out by means of the software SEEP/W (Geo-Slope 1991-2002) with the aim of determining the performance of the draining trench and the pore water distribution in a soil mass, will be illustrated.

EXPERIMENTAL RESULTS AND DISCUSSION

Typical results of the permeability tests carried out on different specimens of the mixture M1 and M2 (similar to MP53-54-55-56, used for measuring the WRC) are shown in Figs. 5 and 6. In the figures, the velocity v and the saturated hydraulic conductivity k_s as a function of the hydraulic gradient i are reported. For both mixtures, velocity and hydraulic conductivity depend on the hydraulic gradient i as found by other researchers (Martin III et al., 2014; West et al. 2016; Valore et al., 2017b). This non linearity depends on the mix of the concrete which influences the flow characteristics such as the tortuosity of the seepage paths, the effective porosity (i.e. the porosity related only to the interconnected pores) and some possible turbulence, etc. (Chandrappa and Biligiri, 2016; West et al., 2016).

For tests performed on the coarser mixture (M1), the saturated hydraulic conductivity k_s ranges from values of about 0.003 m/s, corresponding to the higher values of i reached in the tests (i=5-6), to values of about 0.0085 m/s related to the lower values of i (i=0.1-0.2), as shown in Fig. 5. For tests

249 performed on the finer mixture M2, k_s ranges from values of about 0.0002 m/s for $i \cong 1$ to values of
250 about 0.00035 m/s for $i \cong 0.1$, as reported in Fig. 6.
251 The mean values of saturated hydraulic conductivity k_s obtained for the two mixtures M1 and M2 are
252 summarized in Table 2. For values of the hydraulic gradient ranging between 3 and 6, the permeability
253 k_s of the specimens of mixture M1 ranges from 0.003 to 0.004 m/s, while the permeability of the
254 specimens of mixture M2 is almost constant with values of k_s of about 0.00022 m/s for i ranging
255 between 1 and 6. These values of the coefficient of permeability fall within a permeability range
256 lower than that relative to no-fines concrete used for example for pavement roads (Shaefer et al. 2006;
257 Chen et al., 2008; Haselbach, 2010; Sriravindrarajah et al. 2012; Mrakovcic et al., 2014).

258 Considering that draining trenches are most frequently installed in fine grained soils, such as clays,
259 silts and fine sands in which the seepage velocities are low, and that for practical applications the
260 interesting values of the hydraulic gradient are also low (i=0.1-0.5), both mixtures M1 and M2
261 satisfied the requirement of permeability that the filling material of the trenches must assure.

262 Fig. 7 shows the plot θ versus s, which describes the retention behaviour of the specimens MP53,
263 MP54, MP55 and MP56. The experimental points labelled as "drying" refer to states near to the
264 shrinkage limit and, therefore, these points have been considered to lie on the initial part of the wetting
265 branch. Consequently, no consideration about the magnitude of the loop of hydraulic hysteresis has
266 been made.

267 It is evident that the material reaches very low suction values during wetting at degrees of saturation
268 not higher than 30%. This behaviour is typical of several coarse-grained soils (Cafaro et al., 2008;
269 Bottiglieri, 2009) and for the studied material it seems to be even more marked. This aspect suggests
270 that for this material it is not necessary that the voids between the grains reach full saturation to lead
271 the overall suction to negligible values.

272 The retention curves of the two mixtures have been deduced, according to the van Genuchten model,
273 by fitting the experimental water retention data. The interpolation of the experimental water retention
274 curve has been performed by using the RETC software (van Genuchten et al., 1991), through the use
275 of van Genuchten's and Mualem's models for the retention function (eq.2) and the conductivity
276 function (eq.3), respectively:

277 $$\vartheta_w = \vartheta_r + (\vartheta_s - \vartheta_r)\left[\frac{1}{1+(\alpha(u_a-u_w))^{n'}}\right]^m \qquad \text{(Eq.2)}$$

$$k_w = k_s \left(\frac{1-(\alpha(u_a-u_w))^{n'-2}\left[1+(\alpha(u_a-u_w))^{n'}\right]^{-m}}{\left[1+(\alpha(u_a-u_w))^{n'}\right]^{2n'}} \right) \qquad \text{(Eq.3)}$$

in which θ_s is the saturated volumetric water content, θ_r is the residual water content and α, m, n' are fitting parameters. The parameter n' depends on the pore size distribution (van Genuchten, 1980) and it controls the shape of the curve, the parameter m could be related to the parameter n' through the Mualem model (i.e. m = 1-1/ n') and α is related to the inverse of the air entry suction (m^{-1}).

In the van Genuchten model, the saturated volumetric water content θ_s is the parameter value obtained when the saturation degree is equal to one and the suction value is equal to zero. Actually, different behaviour for soils can be detected in the literature. For example, it has been observed (Cafaro and Cotecchia, 2015) that, for natural clays under wetting, full saturation can be reached not at zero suction, but for a quite high suction value (Fig.8). On the other hand, it has been observed (Leal-Vaca et al., 2012) that, for silty sand under wetting, suction disappears not at full saturation but at a degree of saturation quite low (Fig.9). This experimental evidence should guide the modelling of the WRC. In Fig. 10 a possible framework for porous media under wetting is proposed: for materials with high air entry value, here defined as "right of intermediate behaviour", the van Genuchten model allows to fit the real behaviour by varying the α parameter, while for materials needing positive pore pressure to be fully saturated, here defined as "left of intermediate behaviour", the fitting could involve a volumetric water content at zero suction, θ_0, lower than θ_s.

In this work, in order to fit the retention data of the pervious concrete three different options have been identified:

a) In the first approach, the van Genuchten parameters have been deduced by fixing $\theta_s = n$ (rigid skeleton), for each data set concerning the two mixtures. Following this way, two different WRCs have been obtained, one for each mixture.
b) In the second approach, to overcome the problem related to the relatively poor data sets characterizing each mixture, the van Genuchten parameters have been obtained by optimizing θ_0 for the only data set resulting from joining of the two different sets, due to the similarity of the two mixtures. The result of this fitting approach is a unique common WRC.
c) In the last approach, the van Genuchten parameters have been deduced by fixing a common θ_0 for each data set concerning the two mixtures, but the θ_0 value comes from an optimization procedure using a unique data set arising from the joining of the two different sets. As for the first approach, two different WRCs have been obtained.

The third approach is characterized by the following logical steps:

1) When optimizing the van Genuchten parameters, to obtain two different WRCs, a non consistent $\theta_0 (\theta_0 > \theta_s)$ has been found, probably due to the relatively poor data set of each mixture;

2) For this reason, θ_0 has been fixed as a plausible value by taking only the other parameters under optimization;

3) A plausible $\theta_0$value could be assumed from the literature concerning pervious concrete. Alternatively, it could be optimized by interpolation of a unique data set (MP53-MP54-MP55-MP56) since the two mixtures are quite similar in terms of porosity;

4) In the last case, it is necessary to check if $\theta_0 \leq n$.

The fitting parameters resulting from the above-mentioned approaches are shown in Table 3.

Although the α values are consistent with the air entry range pertaining this type of granular material (Fredlund and Rahardjo, 1993), the differences in the α parameter are not negligible (Table 3). It must be underlined, therefore, that practitioners should not base the design on a unique interpolation approach.

In the following, the "approach *c*" has been used in order to study the impact of the concrete retention properties and related conductivity functions on a boundary value problem.

NUMERICAL RESULTS AND DISCUSSION

In order to deduce by numerical simulation the different hydraulic performance of the two investigated mixtures in a boundary value problem, an ideal model constituted by a natural soil has been defined: the clayey silt of Abate Alonia (Cafaro and Cotecchia, 2015), which forms a horizontal ground level and hosts a draining trench of 12 m deep and 1.5 m wide filled by pervious concrete. The geological features of this soil are described in Cotecchia and Lonoce (1963) and Monterisi (1996). The specific gravity is 2.76, the clay fraction is 8-9% and the in-situ void ratio is about 0.6.

2D FE simulations have been carried out by using the software SEEP/W. The trench has been simulated like rectangular elements 4 m deep (Fig. 11). The lateral boundaries of the mesh have been fixed at a distance of 20 m from the centre. The bottom of the mesh is impermeable and the depth of the model has been set equal to 30 m from the ground level. A water table 13 m deep below ground

level has been set in the analyses and a hydrostatic profile has been assumed for the negative pore pressures.

The soil hydraulic parameters have been obtained through interpolation by using the RETC code and they are shown in Table 4, whereas in Fig. 11 a vertical cross section of the model, reporting the geometry of the draining trench and the initial boundary conditions, is presented. The interceptor drain pipe, in correspondence of which the pore pressure is imposed equal to zero, is schematically represented by the lower end of the trench in Finite Element (FE) calculation.

A wetting path has been hypothesized for the soil, e.g. as a result of an infiltration by rainfall starting from an initial suction profile, and, therefore, the wetting WRCs of the pervious concrete have been accordingly implemented in the FE calculations. A rainfall of intensity equal to 80 mm/d has been assigned at the ground surface for duration of almost 3 days. To deduce the *k(s)* functions, the employed values of the saturated hydraulic conductivity k_s have been: k_s = 0.0075 m/s for mixture M1 and k_s = 0.000285 m/s for mixture M2, based on the graphs of Fig. 5 and Fig. 6, respectively, in correspondence of an assumed hydraulic gradient of about 0.2. To simulate the transient seepage resulting from infiltration, time steps have been generated in the code: number of steps, starting time, initial increment size and expansion factor have been defined in order to obtain both good time resolution at the beginning of the process and clear evolution with time of the overall process.

This numerical analysis has been carried out with two different aims. Firstly, to point out the impact of implementing the WRC and the *k(s)* functions (*Trench Model 1*) on the seepage simulation and, hence, on the variation of pore pressure *u (x, z, t)* with respect to the analysis which, in a simplified way, models the trench as an atmospheric pressure cluster (*Trench Model 2*). This last one is the conventional way to model drains in civil engineering. Secondly, to point out the incidence of the two different pervious concrete mixtures studied when using *Trench Model 1*. Although the numerical results are tied to a specific seepage scheme, they have a useful comparative value which could assist the performance analysis of permeable concrete.

Fig. 12 shows the *pore water pressure u* versus *time* plot from the start of the rainfall, in correspondence of nodes 40, 41, 42 for mixture 1 (M1) only, for both *Trench Model 1* and *Trench Model 2*. It can be observed that for all the considered nodes, the pore pressure increases more rapidly when *Trench Model 2* is implemented in the FE calculation. It is also evident from the plot that for node 42 the suction reaches the value of zero after more than 15 hours in the case of the *Trench Model 1*, whereas for the *Trench Model 2* the suction disappears after almost 6 hours.

When predicting the safety evolution with time, it seems that implementing the hydraulic functions of the drain in the analysis could imply a non-conservative design, since suction slowly disappears. Therefore, in terms of recommendation for practitioners, this realistic approach should be used only for serviceability assessment. In this respect, more accurate numerical analyses should be addressed to study the group effect of the trenches (Cotecchia et al., 2016), the 3D and the slope effects.

As said before, a comparison between numerical predictions obtained by assuming the two different mixtures for the draining trench is also of interest. Fig. 13 reports the *pore pressure* versus *time* plot at nodes 40, 41, 42 (see Fig. 11) for the case of the *Trench Model 1*. It is evident from the plot that for all the monitored nodes the pore pressure predictions are quite similar for both mixtures until about 5-6 hours. Beyond these time values, the pore water pressures predicted with mixture M1 are lower than those predicted with mixture M2.

CONCLUSIONS

In this paper the results of a laboratory investigation on the saturated and unsaturated hydraulic properties of a pervious concrete for deep draining trenches have been reported and discussed. The importance of taking into account the partial saturation of pervious concrete (which fills a trench drain) and surrounding soils when predicting the pore water pressures for a transient regime has been stated, by showing results of numerical modelling of a boundary value problem.

On the basis of the obtained results, the following conclusions can be drawn.

The strength of the pervious concrete, even after only a few days of curing time, is enough to safely build deep trench drains, hence avoiding delays in the excavation of intermediate panels and with advantages in terms of overall costs and efficient construction site planning.

The saturated hydraulic conductivity of both mixtures of pervious concrete tested is high enough and adequate for deep trench drains installed in sandy and fine-grained soils.

The incidence of different ways of fitting the experimental data by using the van Genuchten equation has been shown, although all the calculated fitting parameters seem to be consistent with the values expected for the investigated material grading. In particular, it has been considered that the volumetric water content at zero suction differs from the saturated one and this involves substantial differences for the fitting parameters.

Results of two-dimensional FE calculations have been shown to point out the influence of the hydraulic properties on the modelling of the seepage through a draining trench placed within an ideal unsaturated soil mass during rainfall. The draining trench has been modelled both by implementing

its WRC and the *k(s)* functions and by neglecting them (i.e. conventional approach). Differences in the numerical predictions arise from both the different way of modelling the trench and the different investigated composition for the pervious concrete. Difference in grading for the two investigated mixtures of pervious concrete does not seem to influence the response in terms of pore water pressures significantly, despite their differences in terms of saturated hydraulic conductivity. However, further investigations are necessary to better understand this aspect.

RECOMMENDATIONS AND FUTURE WORK

Recommendations for the design of deep draining trenches filled with pervious concrete can be provided based on this study. When predicting the transient seepage in unsaturated soil mass and, then, the evolution with time of the soil mass stability degree, it appears that implementing the hydraulic functions of the drain in the analyses could imply a non-conservative design. Therefore, this realistic approach should be followed only for serviceability assessment. Moreover, practitioners are suggested to employ several fitting approaches when deducing the WRC of the pervious concrete, since it has been shown the incidence of different interpolation options.

Future work should concern the physical modelling of pervious concrete deep draining trenches, in order to give more general meaning to the element testing results here discussed, given the non negligible variability that pervious concrete can have in-situ. In this respect, the three dimensional variability of the hydraulic and mechanical properties when the concrete is cast in place and involves volumes much greater than those of laboratory specimens should be directly investigated, by in-situ sampling.

ACKNOWLEDGEMENT

The research was carried out with the support from:

MIUR - PRIN 2010-2011: prot. 2010SWTCKC_010

Title: La mitigazione del rischio da frana con interventi sostenibili

Coordinatore Scientifico Nazionale: Prof. Leonardo Cascini UNISA

Responsabile Unità di Palermo: Prof. C. Valore

Title PRIN-UNIPA: L’impiego del calcestruzzo senza frazione fina per la realizzazione di trincee drenanti profonde

REFERENCES

Abadjieva, T., Sephiri, P., (2000). "Investigations on some properties of no-fines concrete." *University of Botswana,* Gabarone.

Alam, B., Javed, M., Ali, Q., Ahmad, N., Ibrahim, M. (2012). "Mechanical properties of no-fines bloated slate aggregate concrete for construction application, experimental study." *Int. J. Civ. Struct. Eng.*, 3(2), 302-308.

ACPT Advanced Concrete Pavement Technology (2012). "Pervious Concrete." *TechBrief December 2012 - FHWA-HFI-13-006. US Department of Transportation Federal Highway Administration.* www.fhwa.dot.gov/pavement/concrete.

Barnhouse, W., Srubar III, W.V. (2016). "Potential for clay clogging of pervious concrete under extreme conditions." *J. Hydrol. Eng*., 15(1), 67-69.

Bottiglieri, O. (2009). "Caratterizzazione idraulica di un terreno a grana media parzialmente saturi*."* *PhD thesis*, Technical University of Bari (In Italian).

Burghignoli, A., Desideri, A. (1987). "On the effectiveness of tubular drains." *Proc. of 9th European Conf. on Soil Mech. and Found. Eng.* - Dublin, Eire, Vol. 1, pp. 149-152.

Cafaro, F., Hoffmann, C., Cotecchia, F., Buscemi, A., Bottiglieri, O., Tarantino, A. (2008). *"*Modellazione del comportamento idraulico di terreni parzialmente saturi a grana media e grossa." *Italian Geotechnical Journal*, 3/2008, 54-72 (In Italian).

Cafaro, F., Cotecchia, F. (2015). "Influence of the mechanical properties of consolidated clays on their water retention curve." *Italian Geotechnical Journal*, 2/2015, 11-27.

Chandler, R. J., Gutierrez, C. I. (1986). "The filter-paper method of suction measurement. Technical Notes." *Géotechnique, 36,* 2, 265-268.

Chandler, R. J., Crilly, M. S., Montgomery-Smith, G. (1992). "A low-cost method of assessing clay desiccation for low-rise buildings." *Proc. Instn. Civ. Engng., n. 2.*

Chandrappa, A.K., Biligiri, K.P. (2016). "Comprehensive investigation of permeability characteristics of pervious concrete: A hydrodynamic approach." *Construction and Building Materials*, 123, 627-637.

Chen, B., Liu, J., Li, P. (2008). "Experimental study on pervious concrete." *Proc. 9th International Conference on Concrete Pavements, San Francisco, California, August 17-21*, 202-211.

Collins, K.A., Hunt, W.F., Hathaway, J.M. (2008). "Hydrological Comparison of Four Types of Permeable Pavement and Standard Asphalt in Eastern North Carolina." *Journal of Hydrological Engr.* Vol. 13, 12, 1146-1157.

Cotecchia, V., Lonoce, R. (1963). "L'erosione nel bacino imbrifero del torrente Rendina e la sedimentazione nel lago artificiale di Abate Alonia." *Geotecnica*, n.1.

467 Cotecchia, F., Lollino, P., Petti, R. (2016). "Efficacy of drainage trenches to stabilise deep slow
468 landslides in clay slopes." *Géotechnique Letters*, 6, 1–6.
469 Coughlin, J.P., Campbell, C.D., Mays, D.C. (2008). "Infiltration and clogging by sand and clay in a
470 pervious concrete pavement system." *Journal of Hydrological Engr.* Vol. 17, 1, 68-73.
471 D'Acunto, B., Urciuoli, G. (2006). "Groundwater regime in a slope stabilized by drain trenches."
472 *Mathematical and Computer modelling*, 43, 754-765. Doi:10.1016/j.mcm.2005.02.013.
473 Deo, O., Sumanasooriya, M., Neithalath, N. (2010). "Permeability reduction in pervious concrete due
474 to clogging: experimental and modeling." *Journal of Materials in Civil Engineering*, ASCE 22, 7,
475 741-751.
476 Di Maio, C., Evangelista, A., Viggiani, G., (1988). "Analisi dell'efficienza di sistemi di dreni
477 tubolari." *Rivista Italiana di Geotecnica*, XXII, 187-199. (In Italian).
478 Fell, R., Mac Gregor, P., Stapledon, D., Bell, G., Foster, M. (2014). "Geotechnical Engineering of
479 Embankment Dams." *2nd edition Chapter 9: Design, specification and construction of filters*, 493-
480 565. CRC Press, London, UK.
481 Fredlund, D.G., Rahardjo, H. (1993). "Soil Mechanics for Unsaturated Soils." *John Wiley & Sons,*
482 *Inc.*
483 Geo-Slope (1991-2002). "SEEP/W version 5 User's Guide." *Geo-Slope Office*.
484 Ghafoori, N., Dutta, S. (1996). "Laboratory investigation of compacted no-fines concrete for paving
485 materials." *Journal of Materials in Civil Engng, ASCE*, 7, 3, 183-191.
486 Goel, P.K. (2006). "Water pollution: Causes, effects and control." *New Age International, New Delhi,*
487 *2006*.
488 González de Vallejo, L.I., Ferrer, M., Ortuño, L., Oteo, C. (2005). "Geoingegneria." *Pearson*
489 *Education Italia S.r.l.*
490 Haselbach, L., Freeman, R.M. (2006). "Vertical Porosity Distribution in Pervious Concrete
491 Pavement." *ACI Materials Journal*, Volume 103, 452-458.
492 Haselbach, L.M., Valavala, S., Montes, F. (2006). "Permeability for sand-clogged Portland cement
493 pervious concrete pavement system." *Journal of Environmental Management*, 81,1, 42-49.
494 Haselbach, L.M. (2010). "Potential for clay clogging of pervious concrete under extreme conditions."
495 *Journal of Hydrologic Engng, ASCE*, 15, 1, 67-69.
496 Haselbach, L., Boyer, M., Kevern, J.T., Schaefer V.R. (2011). "Cyclic heat island impacts on
497 traditional versus pervious concrete pavement systems." *Transportation Research Record: Journal*
498 *of Transportation Research Board*, 2240, 107-115.

Hutchinson, J.N. (1977). "Assessment of the effectiveness of corrective measures in relation to geological conditions and types of slope movement." *Bulletin of the International Association of Engineering Geology*, 16, 131-155.

Kenney, T.C., Pazin, M., Choi, W.S. (1977). "Design of horizontal drains for soil slopes." *Journal of Geotechnical Engineering Division*, Proc. Paper 13366, ASCE 103 (GT11), 1311-1323.

Kevern, J.T. (2006). "Mix design determination for freeze-thaw resistant Portland cement perviuos concrete." *MS thesis. Iowa State University, Ames.*

Kevern, J.T., Schaefer, V.R., Wang, K., and Suleiman, M.T. (2008). "Pervious Concrete Mixture Proportions for Improved Freeze-Thaw Durability." *Journal of ASTM International*, 5, 2, 1-12.

Kevern, J.T., Farney, C. (2012). "Reducing curing requirements for perviuos concrete with a superabsorbent polimer for internal curing." *Transportation Research Record: Journal of the Transportation Research Board, 2290, Transportation Research Record of the National Academies, Washington, D.C.*, pp. 115-121. DOI: 10.3141/2290-15.

Kevern, J.T. (2015). "Evaluating permeability and infiltration requirements for pervious concrete." *Journal of Testing and Evaluation, ASTM*, 43, 3, 544-553.

Lau, K.C., Kenney, T.C. (1984). "Horizontal drains to stabilize clay slopes." *Canadian Geotechnical Journal*, 21,2, 241-249.

Leal-Vaca, J. C., Gallegos-Fonseca, G., Rojas-González, E. (2012). "The decrease of the strength of unsaturated silty sand." *Ingeniería Investigación y Tecnología, volumen XIII (número 4)*, octubre-diciembre 2012: 393-402.

Leonards G.A., (1982) – Investigation of failures. Journal of Geotechnical Engineering Division, ASCE 108, GT2, 222-283.

Mageswari, M., Karthikeyan, M.P., Pavithran, S., Rajkumar, M., Govindarajan, R. (2016). "High strength permeable pavement using no fines concrete." *SSRG International Journal of Civil Engineering*, 3, 3, 62-66.

Mahesh, B., Lavanya, B. (2016). "Experimental study of pervious concrete in pavements." *International Journal of Innovative Research in Science, Engineering and Technology* 5, 7, 12913-12924. DOI:10.15680/IJIRST.2016.0507152.

Martin III, W.D., Putman, B.J., Kaye, N.B. (2013). "Using image analysis to measure the porosity distribution of a porous pavement." *Construction and Building Materials*, 48, 78-84.

Martin III, W.D., Kaye, N.B., Putman, B.J. (2014). "Impact of vertical porosity distribution on the permeability of pervious concrete." *Construction and Building Materials*, 59, 210-217.

Montes, F., Valavala, S., Haselbach, L.M. (2005). "A new test method for porosity measurements of Portland cement pervious." *Journal of ASTM International*, 2, 1, 1-13. https://doi.org/10.1520/JAI12931.

534 Monterisi, L. (1996). "I depositi fluvio-lacustri pleistocenici del torrente Oliveto." *Geol. Appl. e*
535 *Idrogeologia*, Bari, Vol. XXXI.
536 Montes, F., Haselbach, L.M. (2006). "Measuring hydraulic conductivity in pervious concrete*."*
537 *Environmental Engineering Science*, 23, 6, 960-969.
538 Mrakovcic, S., Ceh, N., Jugovac, V. (2014). "Effect of aggregate grading on pervious concrete
539 properties." *Gradevinar*, 66, 2, 107-113. DOI:10.14256/JCE.977.2013.
540 Nakamura, H., (1988). "Landslide control works by horizontal drainage works." *V Int. Symposium*
541 *on Landslides, Lousanne 1988*, 2, 965-970.
542 Neithalath, N. (2004). "Development and characterization of acoustically efficient cementetious
543 materials*." Ph.D. thesis. Purdue University*.
544 Neithalath, N., Sumanasooriya, M.S., Deo, O. (2010). "Characterizing pore volume, sizes, and
545 connectivity in pervious concretes for permeability prediction." *Materials Characterization*, 61, 802-
546 813.
547 Nemirovsky E.M., Welker A.L., Lee R. (2013). "Quantifying evaporation from pervious concrete
548 systems: methodology and hydrologic perspective." *Journal of Irrigation and Drainage*
549 *Engineering, ASCE*, 139, 4, 271–277.
550 Nonveiller, E. (1981). "Efficiency of horizontal drains on slope stability." *Proceedings of 10th*
551 *European Conference on Soil Mechanics and Geotechnical Engineering - Stockholm, Sweden*, Vol.
552 3, pp. 495-500.
553 Pastor, J., Thai, T-H., Francescato, P. (2000). "New bounds for the height limit of a vertical slope."
554 *International Journal for Numerical and Analytical Methods in Geomechanics*, 24, 165-182.
555 Rahardjo, H., Hritzuk, K.J., Leong, E.C., Rezaur, R.B. (2003). "Effectiveness of horizontal drains for
556 slope stability." *Engineering Geology*, 69, 1, 295-308.
557 Ridley, A. M. (1993). "The measurement of soil moisture suction." *PhD thesis, University of London.*
558 Rowe, P.W. (1972). "The relevance of soil fabric to site investigation practice." *Géotechnique* 22(2):
559 195-300.
560 Schaefer, V. R., Wa, K., Suileiman, M. T., Kevern, J. T. (2006). "Mix design development for
561 pervious concrete in cold weather climates." *National Concrete Pavement Technology Center, Iowa*
562 *State University, Ames, IA.*
563 Shu, X., Huang, B., Wu, H., Dong, Q., Burdette, E.G. (2011). "Performance comparison of laboratory
564 and field produced pervious concrete mixture." *Construction and Building Materials*, 25, 3187-3192.
565 Singh, P., Scanlon, A. (2013). "Sustainability of residential concrete." *PHRC - The Pennsylvania*
566 *Housing Research Center. Research Series Report N. 112.*

Sommerville, J., Craig, N., Charles, A. (2011). "No-fines concrete in the UK social housing stock: 50 years on. Structural survey." *Structural Survey, 29, 4, 294-302. Emerald Group Publishing Limited* 0263-080X, DOI 10.1108/02630801111162369.

Sriravindrarajah, R., Huai Wang, N.D., Ervin, L.J.W. (2012). "Mix design for pervious recycled aggregate concrete*." International Journal of Concrete Structure and Materials*, 6, 4, 239-246. DOI 10.1007/s40069-012-0024-x.

Tennis, P., Leming, M.L., Akers, D.J. (2004). "Pervious concrete pavements." *Engineering Bulletin 302.02. Portland Cement Association, Skokie, IL, and National Ready Mixed Concrete Association, Silver Spring, MD.*

Terzaghi K. (1929). "Effects of minor geologic details on the safety of dams." *In: Geology and Engineering for Dams and Reservoirs, American Institute of Mining and Metallurgical Engineers, Technical Publication 215, pp: 31-44. Reprinted in From Theory to Practice in Soil Mechanics. Selection from the writings of Karl Terzaghi. John Wiley & Sons, 1960, New York, London, pp: 119-132.*

Terzaghi, K. (1950). "Mechanism of Landslides." *In: Paige, S. (Ed.), Application of Geology to Engineering Practice. Berkey Volume: Geological Society of America*, pp 83–123.

Thakre, N., Rajput, H., Saxena, J., Mitangale, H. (2014). "Comparative study on strength and permeability of pervious concrete by using nylon and polypropylene fiber*." IJCAT International Journal of Computing and Technology*, 1, 4, 141-148.

Torres, A., Hu, J., Ramos, A. (2015). "The effect of the cementitious paste thickness on the performance of pervious concrete." *Construction and Building Materials*, 95, 850-859.

Tsao, T.M., Wang, M.K., Chen, M.C., Takeuchi, Y., Matsuura, S., Ochiai, H. (2005). "A case study of the pore water pressure fluctuation on the slip surface using horizontal borehole works on drainage well." *Engineering Geology*, 78, 105-118.

Ushane, K. S., Kumar, K.J.P., Kaviths, C. (2014). "Investigation of no-fines concrete in building blocks*." IJSCE International Journal of Structural and Civil Engineering Research*, 3, 4, 170-177.

Valore, C., Ziccarelli, M., (2015). "The stabilization of a slope-viaduct system without closing traffic." *Proceedings of 16th European Conference on Soil Mechanics and Geotechnical Engineering - Edinburg, Scotland, 13-17 September 2015*. pp. 367-372. ISBN: 978-0-7277-6067-8; doi:10.1680/ecsmge.60678.

Valore, C., Ziccarelli, M., Muscolino, S.R. (2017a). "The bearing capacity of footings on sand with a weak layer." *Geotechnical Research*, 4,1, 12-29. http://dx.doi.org/10.1680/jgere.16.00020.

Valore, C., Ziccarelli, M., Muscolino, S.R. (2017b). "An experimental investigation into the permeability and filter properties of pervious concrete for deep draining trenches." *Accepted for publication in the Italian Geotechnical Journal.*

van Genuchten, M. Y. (1980). "A closed form equation for predicting the hydraulic conductivity of unsaturated soils." *Soil Sci. Soc. Am. J. 44,* No. 5

van Genuchten, M. Th., Leij, F.J.,Yates, S.R. (1991). "The RETC Code for Quantifying the Hydraulic Functions of Unsaturated Soils, Version 1.0." *EPA Report 600/2-91/065, U.S. Salinity Laboratory, USDA, ARS, Riverside, California.*

West, D., Kaye, N.B., Putman, B.J., Clark, R. (2016). "Quantifying the non-linear hydraulic behavior of pervious concrete." *Journal of Testing and Evaluation*, 44, 4, 2172-2181.

Zhong, R., Wille, K. (2016). "Compression response of normal and high strength pervious concrete." *Constructions and Building Materials*, 109, 177-187.

Ziccarelli, M., Valore, C., Muscolino, S.R., Fioravante V. (2017). "Centrifuge tests on strip footings on sand with a weak layer." *Geotechnical Research*, 4,1, 47-64. http://dx.doi.org/10.1680/jgere.16.00021.

Table 1. Physical characteristics of the specimens of pervious concrete subjected to tests

Mixture		M1	M2
Specimens		MP53 and MP55	MP54 and MP56
Specific gravity (Gs)	-	2.62	2.65
Solid unit weight of aggregates (γ_s)	(kN/m^3)	26.7	26
Water - cement ratio (*W/C*)	-	0.4	0.4
Cement content (amount of cement per 1 m^3 of pervious concrete) (*C*)	(kg/m^3)	161.4	169.6
Dry unit weight (γ_d)	(kN/m^3)	16.4	16.5
Porosity (*n*)	(%)	39.7	37.6
Aggregates weight - total weight ratio(A/W_t)	(%)	88.5	88.5
Aggregates weight - cement ratio (*A/C*)	(%)	10.8	10.9
Water weight - total weight ratio (W/W_t)	(%)	3.29	3.28
Cement weight - total weight ratio (C/W_t)	(%)	8.23	8.21

Table 2. Saturated permeability of the two mixtures.

Mixture	k_s (m/s)	Ranges of hydraulic gradient *i*
M1	0.004	3 ÷ 6
	0.006	3 ÷ 0.1
M2	0.0002	1 ÷ 6
	0.00025	1 ÷ 0.1

Table 3. Fitting parameters for M1 and M2 experimental water retention curve: a) Approach a; b) Approach b; c) Approach c

a)

Mixture	θ_r	$\theta_S = n$	α (m^{-1})	n′	m = 1-1/n′	l
1	0.01	0.4	98.55	1.5	0.33	0.5
2	0.01	0.38	73.15	1.45	0.31	0.5

b)

Mixture	θ_r	θ_0	α (m^{-1})	n′	m = 1-1/n′	l
1 + 2	0.01	0.12	4.21	1.49	0.33	0.5

c)

Mixture	θ_r	$\theta_0 < n$	α (m^{-1})	n′	m = 1-1/n′	l
1	0.01	0.12	6.3	1.5	0.33	0.5
2	0.01	0.12	3.2	1.5	0.33	0.5

692

693

694

695 **Table 4**. WRC fitting parameters for the Clayey Silt of Abate Alonia (Cafaro and Cotecchia, 2015)

θ_r	θ_0	$\alpha(m^{-1})$	n'	$m=1-1/n'$	l
0.1	0.358	0.005	1.73	0.42	0.5

696

697

698

Table captions
Click here to download Table MTENG-6264-SEPT17 Table captions.docx

LIST OF TABLES

Table 1. Physical characteristics of the specimens of pervious concrete subjected to tests.

Table 2. Saturated permeability of the two mixtures

Table 3. Fitting parameters for M1 and M2 experimental water retention curve: a) Approach a; b) Approach b; c) Approach c

Table 4. WRC fitting parameters for the Clayey Silt of Abate Alonia (Cafaro and Cotecchia, 2015)

Figure 1

Click here to download Figure Figure 1.tif




Figure 2

Click here to download Figure Figure 2.tiff






Figure 3

Click here to download Figure Figure 3.tiff



(a)



(b)

Figure 4

Click here to download Figure Figure 4.tiff




Figure 5

Click here to download Figure Figure 5.tif




Figure 6

Click here to download Figure Figure 6.tiff




Figure 7

Click here to download Figure Figure 7.tiff




Figure 8

Click here to download Figure Figure 8.tiff




Figure 9

Click here to download Figure figure 9.tiff




Figure 10

Click here to download Figure Figure 10.tiff




Figure 11

Click here to download Figure Figure 11.tif




Figure 12

Click here to download Figure Figure 12.tif





Figure 13

Click here to download Figure Figure 13.tif



LIST OF FIGURES

Fig. 1. Schematic representation of the realisation phases of a deep draining trench

Fig. 2. Grain-size distribution of aggregates of mixtures M1 and M2 to which belong the specimens MP53 and MP55 and MP54 and MP56 respectively

Fig. 3. Specimens MP53 and MP54 (a) and specimens MP55 and MP56 (b) with PVC rings used for their preparation

Fig. 4. Typical results of uniaxial compression tests on specimens of the mixture M1 and M2, after 28 days curing time in air

Fig. 5. Typical results of head falling permeability tests on specimens of mixture M1

Fig. 6. Typical results of head falling permeability tests on specimens of mixture M2

Fig. 7. Drying and Wetting tests on specimens MP53, MP54, MP55, MP56

Fig. 8. Drying-Wetting cycle of a specimen of Montemesola natural clay (from Cafaro and Cotecchia, 2015, modified)

Fig. 9 . Drying-Wetting data of a Silty Sand (from Leal-Vaca et al., 2012, redrawn)

Fig. 10. A possible framework for porous media under wetting

Fig. 11. Vertical cross section of the model: geometry, boundary conditions and initial conditions

Fig. 12 . Pore pressure versus Time at nodes 40,41,42 for both Trench Model 1 and Trench Model 2 (Mixture M1)

Fig. 13. Pore pressure versus Time at nodes 40, 41, 42 for both mixtures (Trench Model 1)

Copyright Agreement

Click here to download Copyright Agreement ASCE Sept 2017 Copyrigth CAFARO.pdf

ASCE Authorship, Originality, and Copyright Transfer Agreement

Publication Title: JOURNAL OF MATERIALS IN CIVIL ENGINEERING

Manuscript Title: HYDRAULIC CHARACTERIZATION OF A PERVIOUS CONCRETE FOR DEEP DRAINING TRENCHES

Author(s) – **Names, postal addresses, and e-mail addresses of all authors**

1) VALENTINA MARZULLI – INSTITUTE FOR MULTISCALE SIMULATION – Nägelsbachstrasse 49b – 91052 ERLANGEN (GERMANY) – valentina.marzulli@fau.de

2) FRANCESCO CAFARO – Politecnico di Bari DICATECH – Via Orabona 4 – 70125 BARI (ITALY) francesco.cafaro@poliba.it

3) MAURIZIO ZICCARELLI – Università di Palermo DICAM – Viale delle Scienze – Edificio 8 – 90128 PALERMO (ITALY) – maurizio.ziccarelli@unipa.it

I. Authorship Responsibility

To protect the integrity of authorship, only people who have significantly contributed to the research or project and manuscript preparation shall be listed as coauthors. The corresponding author attests to the fact that anyone named as a coauthor has seen the final version of the manuscript and has agreed to its submission for publication. Deceased persons who meet the criteria for coauthorship shall be included, with a footnote reporting date of death. No fictitious name shall be given as an author or coauthor. An author who submits a manuscript for publication accepts responsibility for having properly included all, and only, qualified coauthors.

I, the corresponding author, confirm that the authors listed on the manuscript are aware of their authorship status and qualify to be authors on the manuscript according to the guidelines above.

FRANCESCO CAFARO — September 27th, 2017

Print Name — Signature — Date

II. Originality of Content

ASCE respects the copyright ownership of other publishers. ASCE requires authors to obtain permission from the copyright holder to reproduce any material that (1) they did not create themselves and/or (2) has been previously published, to include the authors' own work for which copyright was transferred to an entity other than ASCE. Each author has a responsibility to identify materials that require permission by including a citation in the figure or table caption or in extracted text. Materials re-used from an open access repository or in the public domain must still include a citation and URL, if applicable. At the time of submission, authors must provide verification that the copyright owner will permit re-use by a commercial publisher in print and electronic forms with worldwide distribution. For Conference Proceeding manuscripts submitted through the ASCE online submission system, authors are asked to verify that they have permission to re-use content where applicable. Written permissions are not required at submission but must be provided to ASCE if requested. Regardless of acceptance, no manuscript or part of a manuscript will be published by ASCE without proper verification of all necessary permissions to re-use. ASCE accepts no responsibility for verifying permissions provided by the author. Any breach of copyright will result in retraction of the published manuscript.

I, the corresponding author, confirm that all of the content, figures (drawings, charts, photographs, etc.), and tables in the submitted work are either original work created by the authors listed on the manuscript or work for which permission to re-use has been obtained from the creator. For any figures, tables, or text blocks exceeding 100 words from a journal article or 500 words from a book, written permission from the copyright holder has been obtained and supplied with the submission.

FRANCESCO CAFARO — September 27th, 2017

Print name — Signature — Date

III. Copyright Transfer

ASCE requires that authors or their agents assign copyright to ASCE for all original content published by ASCE. The author(s) warrant(s) that the above-cited manuscript is the original work of the author(s) and has never been published in its present form.

The undersigned, with the consent of all authors, hereby transfers, to the extent that there is copyright to be transferred, the exclusive copyright interest in the above-cited manuscript (subsequently called the "work") in this and all subsequent editions of the work (to include closures and errata), and in derivatives, translations, or ancillaries, in English and in foreign translations, in all formats and media of expression now known or later developed, including electronic, to the American Society of Civil Engineers subject to the following:

- The undersigned author and all coauthors retain the right to revise, adapt, prepare derivative works, present orally, or distribute the work, provided that all such use is for the personal noncommercial benefit of the author(s) and is consistent with any prior contractual agreement between the undersigned and/or coauthors and their employer(s).
- No proprietary right other than copyright is claimed by ASCE.
- If the manuscript is not accepted for publication by ASCE or is withdrawn by the author prior to publication (online or in print), this transfer will be null and void.
- Authors may post a PDF of the ASCE-published version of their work on their employers' ***Intranet*** with password protection. The following statement must appear with the work: "This material may be downloaded for personal use only. Any other use requires prior permission of the American Society of Civil Engineers."
- Authors may post the ***final draft*** of their work on open, unrestricted Internet sites or deposit it in an institutional repository when the draft contains a link to the published version at www.ascelibrary.org. "Final draft" means the version submitted to ASCE after peer review and prior to copyediting or other ASCE production activities; it does not include the copyedited version, the page proof, a PDF, or full-text HTML of the published version.

Exceptions to the Copyright Transfer policy exist in the following circumstances. Check the appropriate box below to indicate whether you are claiming an exception:

☐ **U.S. GOVERNMENT EMPLOYEES:** Work prepared by U.S. Government employees in their official capacities is not subject to copyright in the United States. Such authors must place their work in the public domain, meaning that it can be freely copied, republished, or redistributed. In order for the work to be placed in the public domain, ALL AUTHORS must be official U.S. Government employees. If at least one author is not a U.S. Government employee, copyright must be transferred to ASCE by that author.

☐ **CROWN GOVERNMENT COPYRIGHT:** Whereby a work is prepared by officers of the Crown Government in their official capacities, the Crown Government reserves its own copyright under national law. If ALL AUTHORS on the manuscript are Crown Government employees, copyright cannot be transferred to ASCE; however, ASCE is given the following nonexclusive rights: (1) to use, print, and/or publish in any language and any format, print and electronic, the above-mentioned work or any part thereof, provided that the name of the author and the Crown Government affiliation is clearly indicated; (2) to grant the same rights to others to print or publish the work; and (3) to collect royalty fees. ALL AUTHORS must be official Crown Government employees in order to claim this exemption in its entirety. If at least one author is not a Crown Government employee, copyright must be transferred to ASCE by that author.


☐ **WORK-FOR-HIRE:** Privately employed authors who have prepared works in their official capacity as employees must also transfer copyright to ASCE; however, their employer retains the rights to revise, adapt, prepare derivative works, publish, reprint, reproduce, and distribute the work provided that such use is for the promotion of its business enterprise and does not imply the endorsement of ASCE. In this instance, an authorized agent from the authors' employer must sign the form below.

☐ **U.S. GOVERNMENT CONTRACTORS:** Work prepared by authors under a contract for the U.S. Government (e.g., U.S. Government labs) may or may not be subject to copyright transfer. Authors must refer to their contractor agreement. For works that qualify as U.S. Government works by a contractor, ASCE acknowledges that the U.S. Government retains a nonexclusive, paid-up, irrevocable, worldwide license to publish or reproduce this work for U.S. Government purposes only. This policy DOES NOT apply to work created with U.S. Government grants.

I, the corresponding author, acting with consent of all authors listed on the manuscript, hereby transfer copyright or claim exemption to transfer copyright of the work as indicated above to the American Society of Civil Engineers.

FRANCESCO CAFARO

Print Name of Author or Agent



September 27th, 2017

Signature of Author of Agent Date

More information regarding the policies of ASCE can be found at http://www.asce.org/authorsandeditors

Response to Reviewers Comments
Click here to download Response to Reviewers Comments
MTENG 6264 Reply-NOVEMBER6.docx

REPLY TO EDITOR

Authors wish to thank the Editor and the Reviewers for their comments.
In this last version of the manuscript, changes of the old manuscript only concern the Conclusions, in which a sentence providing recommendation and a sentence describing research perspectives have been removed and, partially modified, put into a new final section, as required by a reviewer.
Moreover, in this last short section, named “Recommedations and Future Work”, the Authors have provided further comments based on what discussed in the other sections of the paper.
Best regards.

The corresponding author.